

Estimation cost sent to me:

**COST ESTIMATION OF CONSTRUCTING A PRIMARY SCHOOL JINKFUIN,  
CAMEROON.**

NO	ITEM	Description	Number	Cost Per 1	Total Cost
<b>Foundation</b>					
1.	Pegging	Timber, 2 x 4	30	1000 FRS CFA	30000 FRS CFA
2.	Excavation	-	-	-	30 000 FRS
3.	Stones	4 double Trips	4	60 000 FRS	240 000 FRS
4.	Rods	Diameter 10	25	6000 FRS	150 000 FRS.
		Diameter 6	15	1500	22500 FRS
	Binding Wire	10 rolls	10	15000	15000 Frs.
5.	Cement	100 Bags	100	6500 FRS	650 000 FRS
6.	Sand	1 double trip	1	150 000	150 000 FRS
7.	Gravel	I double trip	1	150 000 FRS	150 000 FRS
8.	Sun dried bricks	-	2000	25 FRS	50 000 FRS
9.	Frames	2 windows, 1 door	5	5000	25000 FRS
10.	Timber Boards	1 x 12	20	3000	60 000 FRS
11.	Pole lines	2 x 2	70	700	49 000 FRS
12.	Rafters	2 x 4	60	1000	60 000 FRS
13.	Corrugated sheets	2 meters	1 1/2	400 000	400 000 FRS
14.	Zinc Nails	5 Packets	5	5500	27500 FRS
15.	3 Inches, 4 inches nails	4 packets 3 inches, 3 packet 4 inches	7	2500	17500 frs
16.	Gaskets	10 packets	10	1000	10 000 FRS
17.	Toolbar Zinc	8 sheets	8	20 000	160 000 FRS
18.	Ridging	4 sheets	4	10 000	40 000 FRS CFA
19.	Table/chairs	5 tables, 5 chairs	10	7000	70 000 FRS
20.	Cupboard	1	1	25000	25000 FRS

<b>21.</b>	<b>Workmanship</b>	<b>Bricklayers/ carpenters</b>	<b>1</b>	<b>250 000 FRS</b>	<b>250 000 FRS</b>
------------	--------------------	------------------------------------	----------	------------------------	------------------------

Total Cost for One Classroom: 2. 681 500 FRS CFA.

Total Cost For Five Classrooms: 2681 500 x 5: 13 407 500 FRS CFA.